

864 HH Fireplace

Featuring the



Tested and Listed by



OMNI-Test Laboratories, Inc. Beaverton, Oregon Report # 028-F-59b-5 ANSI Z21.88b-2003

- Built-In Direct Vent Fireplace
- Natural Gas or Propane
- Residential or Mobile Home

WARNING: If the information in these instructions is not followed exactly, a fire or explosion may result causing property damage, personal injury or loss of life.

- Do not store or use gasoline or other flammable vapors and liquids in the vicinity of this or any other appliance.

WHAT TO DO IF YOU SMELL GAS

- · Do not try to light any appliance.
- Do not touch any electrical switch; do not use any phone in your building.
- Immediately call gas supplier from a neighbor's phone. Follow the gas supplier's instructions.
- If you cannot reach your gas supplier, call the fire department.
- Installation and service must be performed by a qualified installer, service agency or the gas supplier.

This appliance may be installed as an OEM installation in a manufactured (mobile) home and must be installed in accordance with the manufacturer's instructions and the manufactured home construction and safety standard, Title 24 CFR, Part 3280.

This appliance is only for use with the type(s) of gas indicated on the rating plate. A conversion kit is supplied with the appliance.

Installation Manual

INSTALLER: Leave this manual with the appliance. CONSUMER: Retain this manual for future reference.



TRAVIS INDUSTRIES HOUSE OF FIRE

4800 Harbour Pointe Blvd. SW Mukilteo, WA 98275

Overview

This manual details the installation requirements for the 864 HH (Home Heater) fireplace. For operating and maintenance instructions, refer to the 864 HH Owner's Manual (part # 100-01181).

Listing Details

This appliance was listed by OMNI-Test Laboratories, Inc. to ANSI Z21.88 - report # 028-F-59b-5. The listing label is attached to the appliance near the gas control valve. A copy is shown to the right.

IAS (ICBO) Approval

This appliance was listed by OMNI-Test Laboratories, Inc. - IAS # TL130 (previously ICBO).

Massachusetts Approval

This manual has been submitted to the Massachusetts Board of State Examiners of Plumbers and Gas Fitters

National Fireplace Institute



We suggest that our gas hearth products be installed and serviced by professionals who are certified in the U.S. by the National Fireplace Institute® (NFI) as NFI Gas Specialists.

N.G. 7." 3.5." Sides to enclosure Top to enclosure (from stand-offs)..... Base of Fireplace to an 8" Mantel (see manual for other mantel depths)... Manifold Pressure on "HI" (inches W.C.) Minimum Inlet Pressure (inches W.C.) Maximum Inlet Pressure (inches W.C.) Minimum Clearances to Combustibles Back to enclosure 0.5" Wood Floor Beneath Fireplace ... 0" Input Rate on "HI" (BTU/Hr)..... Input Rate on "LO" (BTU/Hr).... Fireplace Face to Adjacent Wall This vented gas fireplace heater is equipped at the factory for use with natural gas. If conversion to propane (LP) is desired, the optional actory conversion kit must be used. for use with the type of gas indicated on the rating plate and may be installed in an aftermarket, undeduced the most manual for details. This appliance is in other gases, unless a retified fit is used. llation in Manufactured or Mobile Homes must conform with Manufactured Home Construction and Safety Standard, Title 24 CFR,

For natural gas when equipped with the following drill size orifice: DMS 45 Front - 45 Back For propane when equipped with the following drill size orifice: 1.2 mm Front - DMS 55 Back This appliance is equipped for use only at altitudes 0-2,000 feet. This appliance must be properly connected to a venting system in accordance with the manufacturer's installation instructions. Use only approved coaxial direct vent system to vent this appliance to the exterior, See owner's manual for approved brands of venting.

For altitudes above 2,000 feet, the vent configuration, orifice, or combination of both may need to be changed. See the owner's manual for information on making these changes. Electrical Rating: 115v, 1.5 Amps, 60 Hz WARNING: Improper installation, adjustment, alteration, service or maintenance can cause injury or property damage. Refer to the owner's information manual provided with this appliance. For assistance or additional information consult a qualified installer, service agency or

Jul Aug Sep Apr May Jan Teb 2006 2007 2008 Manufacture Date:

S oct Dec

4800 Harbour Pointe Blvd. SW Mukilteo, WA 98275

TRAVIS INDUSTRIES HOUSE OF FIRE

VENTED GAS FIREPLACE HEATER – NOT FOR USE WITH SOLID FUEL

the gas supplier.

This vented gas fireplace heater is not for use with air filters.

Keep children, clothing, furniture, gasoline and other liquids having flammable vapors away. Do not operate this appliance with glass removed, cracked or broken. Replacement of the

TION: Hot while in operation. Do not touch. Severe burns may result. banel(s) should be done by a licensed or qualified service person

<u>Introduction</u>	Installation (continued)	
Overview2	Hearth Requirements	. 32
Listing Details2	Facing Requirements	. 33
· ·	Drywall Installation	
Safety Precautions	Facing Overview	
	Optional Faceplates – Sizing Chart	
Safety Precautions4	Thin Facing Installation	
	Thick Facing Installation	. 37
Features and Specifications	Thick Facing Installation with FPX Arched Faces	. 38
Features	Mantel Requirements	. 40
Installation Options	Install Example - Build-Out (Dog-House) w Hor. Term	. 4
Heating Specifications 6	Install Example - Build-In w Hor. Term	. 42
Dimensions 6		
Differsions		
Installation	Finalizing the Installation	
	Steps for Finalizing the Installation	
Packing List7	Starting the Pilot Flame	
Additional Items Required7	Pilot Flame Inspection	
Installation Overview7	Air Shutter Adjustment	
Recommended Installation Procedure7	Glass Frame Removal and Installation	
Massachusetts Requirements8	Fireback and Grate Installation	
Converting the Fireplace to Top Vent Configuration9	Log Set Installation	
Fireplace Placement Requirements11	LP Conversion Instructions	. 52
Clearances11		
Raised Fireplaces11	Optional Equipment	
Min. Framing Dims Rear Vent Configuration12		_,
Min. Framing Dims Top Vent Configuration13	Grill Installation	
Nailing Brackets14	Remote Control Receiver Installation (2 Options)	
Corner Installations - Rear Vent Configuration15	Extra Room Power Heat Duct	
Corner Installations - Top Vent Configuration16	Accent Light Installation (sku 94400100)	. 64
Gas Line Requirements17		
Fuel17	Index	
Gas Line Connection17	Index	69
Gas Inlet Pressure17	IIIuex	. 00
Gas Line Location17		
Electrical Connection (required)19		
Wall Switch or Thermostat Installation20		
Wiring Diagram (Millivolt System)20		
Wall Switch Installation20		
Vent Requirements21		
Vent Clearances21		
Altitude Considerations21		
Approved Vent22		
Vent Installation22		
Approved Vent Configurations23		
Restrictor Position23		
Exhaust Restrictor Adjustment23		
Intake Restrictor Adjustment24		
Diffuser Plate Adjustment25		
Rear Vent Config. W Horizontal Term. (no vertical rise) . 26		
Rear Vent Config. W Horizontal Term. (w vertical rise)27		
Rear Vent Configuration with Vertical Termination28		
Top Vent Configuration with Horizontal Termination29		
Top Vent Configuration with Vertical Termination30		
Tormination Dequirements		

Safety Precautions

Safety Warnings:

- Failure to follow all of the requirements may result in property damage, bodily injury, or even death.
- This unit must be installed by a qualified installer to prevent the possibility of an explosion.
- This appliance must be installed in accordance with all local codes, if any; if not, in U.S.A. follow ANSI Z223.1 and NFPA 54(88).
- In Manufactured or Mobile Homes must confirm with: In USA, Manufactured Home Construction and Safety Standard, Title 24 CFR, Part 3280, or, when such a standard is not applicable, the Standard for Manufactured Home Installations, ANSI/NCSBCS A225.1. This appliance may be installed in Manufactured Housing only after the home is site located.
- All exhaust gases must be vented outside the structure of the living-area. Combustion air is drawn from outside the living-area structure.
- Notify your insurance company before hooking up this fireplace.
- The room heater should be inspected before use and at least annually by a qualified service person. More frequent cleaning may be required due to excessive lint from carpeting, bedding material, etc.
- The instructions in this manual must be strictly adhered to. Do not use makeshift methods or compromise in the installation. Improper installation will void the warranty and safety listing.
- This heater is approved for use with natural gas (NG) or propane (LP). Burning the incorrect fuel will void the warranty and safety listing and may cause an extreme safety hazard. Direct questions about the type of fuel used to your dealer. Check the label and flame adjust knob on the gas control valve.
- Contact your local building officials to obtain a permit and information on any installation restrictions or inspection requirements in your area.
- If the flame becomes sooty, dark orange in color, or extremely tall, do not operate the heater. Call your dealer and arrange for proper servicing.
- It is imperative that control compartments, screens, or circulating air passageways of the heater be kept clean and free of obstructions. These areas provide the air necessary for safe operation.
- Do not operate the heater if it is not operating properly in any fashion or if you are uncertain. Call your dealer for a full explanation of your heater and what to expect.
- Do not store or use gasoline or other flammable liquids in the vicinity of this heater.
- Do not operate if any portion of the heater was submerged in water or if any corrosion occurs.
- Do not place clothing or other flammable items on or near the heater. Because this heater can be controlled by a thermostat there is a possibility of the heater turning on and igniting any items placed on or near it.
- Light the heater using the built-in piezo igniter. Do not use matches or any other external device to light your heater.
- Never remove, replace, modify or substitute any part of the heater unless instructions are given in this
 manual. All other work must be done by a trained technician. Don't modify or replace orifices.
- The viewing glass should be opened only for lighting the pilot or conducting service.
- Any safety screen or guard removed for servicing must be replaced prior to operating the heater.

Safety Precautions

Safety Warnings (continued):

- Allow the heater to cool before carrying out any maintenance or cleaning.
- Operate the heater according to the instructions included in this manual.
- If the main burners do not start correctly turn the gas off at the gas control valve and call your dealer for service.
- The pilot flame must contact the thermopile and thermocouple. If it does not, turn the gas control valve to "OFF" and call your dealer.
- This unit is not for use with solid fuel.
- Do not place anything inside the firebox (except the included logs).
- If the fiber logs become damaged, replace with Travis Industries log set.
- Do not throw this manual away. This manual has important operating and maintenance instructions
 that you will need at a later time. Always follow the instructions in this manual.
- Do not touch the hot surfaces of the heater. Educate all children of the danger of a high-temperature heater. Young children should be supervised when they are in the same room as the heater.
- Due to the high temperature, the heater should be located out of traffic and away from furniture and draperies.
- Instruct everyone in the house how to shut gas off to the appliance and at the gas main shutoff valve.
 The gas main shutoff valve is usually next to the gas meter or propane tank and requires a wrench to shut off.
- Travis Industries, Inc. grants no warranty, implied or stated, for the installation or maintenance of your heater, and assumes no responsibility of any consequential damage(s).

Installation Options

- · Residential or Mobile Home
- Straight or Corner Placement
- Flush or Recessed Face


- Raised or Floor Placement
- Internal or External Chase
- · Horizontal or Vertical Vent
- Bedroom Approved

Heating Specifications

	Naturai Gas	Propane
Approximate Heating Capacity (in square feet)*	1,200 to 2,250	1,200 to 2,250
Maximum BTU Input Per Hour	40,000	39,000
Steady State Efficiency** (with blowers on)	Up to 80 %	Up to 81 %

- * Heating capacity will vary with floor plan, insulation, and outside temperature.
- ** Efficiency rating is a product thermal efficiency rating determined under continuous operation independent of installed system.

Dimensions



Packing List

- Propane Conversion Kit
- Log Set (9 piece)
- Grate

- Wall Switch with Wire (see page 20 for details)
- Firestop (sku 93006094)


Additional Items Required


- FIREBACKS ARE REQUIRED See page 47. (sku 98500662, 98500663, 98500664, or 98500665)
- Direct Vent
- Gas Line Equipment (shutoff valve, pipe, etc.)
- Electrical Equipment (min. 14 gauge, grounded line)
- Grill

Installation Overview

All requirements below must be met.

Top Vent Configuration





Recommended Installation Procedure

- Frame the opening for the fireplace. Make sure to allow for vent installation.
- This fireplace is designed to accommodate 1/2" or 5/8" drywall (see "Nailing Brackets" on page 14 for details). Secure the fireplace to the framing.
- Install the vent, gas line and electrical hook-up.
- Install the wall switch (see page 20) or thermostat (if applicable).
- Install the drywall.
- Install the hearth (if applicable).
- Install the facing (if applicable).
- Install the mantel (if applicable).
- Finalize the installation (see page 43) and install the grill or face.

Installation (for qualified installers only)

Massachusetts Requirements

NOTE: The following requirements reference various Massachusetts and national codes not contained in this document.

Requirements for the Commonwealth of Massachusetts

For all side wall horizontally vented gas fueled equipment installed in every dwelling, building or structure used in whole or in part for residential purposes, including those owned or operated by the Commonwealth and where the side wall exhaust vent termination is less than seven (7) feet above finished grade in the area of the venting, including but not limited to decks and porches, the following requirements shall be satisfied:

Installation of Carbon Monoxide Detectors

At the time of installation of the side wall horizontal vented gas fueled equipment, the installing plumber or gasfitter shall observe that a hard wired carbon monoxide detector with an alarm and battery back-up is installed on the floor level where the gas equipment is to be installed. In addition, the installing plumber or gasfitter shall observe that a battery operated or hard wired carbon monoxide detector with an alarm is installed on each additional level of the dwelling, building or structure served by the side wall horizontal vented gas fueled equipment. It shall be the responsibility of the property owner to secure the services of qualified licensed professionals for the installation of hard wired carbon monoxide detectors.

In the event that the side wall horizontally vented gas fueled equipment is installed in a crawl space or an attic, the hard wired carbon monoxide detector with alarm and battery back-up may be installed on the next adjacent floor level.

In the event that the requirements of this subdivision can not be met at the time of completion of installation, the owner shall have a period of thirty (30) days to comply with the above requirements; provided, however, that during said thirty (30) day period, a battery operated carbon monoxide detector with an alarm shall be installed.

Approved Carbon Monoxide Detectors

Each carbon monoxide detector as required in accordance with the above provisions shall comply with NFPA 720 and be ANSI/UL 2034 listed and IAS certified.

Signage

A metal or plastic identification plate shall be permanently mounted to the exterior of the building at a minimum height of eight (8) feet above grade directly in line with the exhaust vent terminal for the horizontally vented gas fueled heating appliance or equipment. The sign shall read, in print size no less than one-half (1/2) inch in size, "GAS VENT DIRECTLY BELOW. KEEP CLEAR OF ALL OBSTRUCTIONS".

Inspection

The state or local gas inspector of the side wall horizontally vented gas fueled equipment shall not approve the installation unless, upon inspection, the inspector observes carbon monoxide detectors and signage installed in accordance with the provisions of 248 CMR 5.08(2)(a)1 through 4.

Exemptions

The following equipment is exempt from 248 CMR 5.08(2)(a)1 through 4:

- The equipment listed in Chapter 10 entitled "Equipment Not Required To Be Vented" in the most current edition of NFPA 54 as adopted by the Board; and
- Product Approved side wall horizontally vented gas fueled equipment installed in a room or structure separate from the dwelling, building or structure used in whole or in part for residential purposes.

MANUFACTURER REQUIREMENTS

Gas Equipment Venting System Provided

When the manufacturer of Product Approved side wall horizontally vented gas equipment provides a venting system design or venting system components with the equipment, the instructions provided by the manufacturer for installation of the equipment and the venting system shall include:

- -- Detailed instructions for the installation of the venting system design or the venting system components; and
- -- A complete parts list for the venting system design or venting system.

Gas Equipment Venting System NOT Provided

When the manufacturer of a Product Approved side wall horizontally vented gas fueled equipment does not provide the parts for venting the flue gases, but identifies "special venting systems", the following requirements shall be satisfied by the manufacturer:

- -- The referenced "special venting system" instructions shall be included with the appliance or equipment installation instructions; and
- -- The "special venting systems" shall be Product Approved by the Board, and the instructions for that system shall include a parts list and detailed installation instructions.

A copy of all installation instructions for all Product Approved side wall horizontally vented gas fueled equipment, all venting instructions, all parts lists for venting instructions, and/or all venting design instructions shall remain with the appliance or equipment at the completion of the installation.

See "Gas Line Requirements" on page17 for additional Massachusetts requirements.

Top Vent or Rear Vent Configuration


This appliance is shipped in the rear vent configuration. To change to the top vent configuration, follow the directions below.

NOTE: the vent configuration affects several aspects of installation (framing, maximum vent rise, maximum vent run). When reviewing the installation requirements make sure to pay attention to the type of configuration being used.

Converting the Fireplace to Top Vent Remove the 4 screws securing the cover plate. Configuration Remove the 4 screws Remove it and place it securing the cover plate (with aside. This part may be discarded. Remove the 4 screws securing the intake cover plate. Remove it and place it aside. Remove and discard all of the insulation found near the flue assembly (make sure to remove every piece).

Installation (for qualified installers only)

Converting the Fireplace to Top Vent (continued)



Fireplace Placement Requirements


- The fireplace requires a 1/2" clearance from the angled sides and back of the fireplace to the framing members. No material (insulation, framing, etc.) may be placed into this area.
- Fireplace must be installed on a level surface capable of supporting the fireplace and vent
- Fireplace must be placed directly on wood or non-combustible surface (not on linoleum or carpet)
- This heater may be placed in a bedroom. Please be aware of the large amount of heat this appliance produces when determining a location.

Clearances


- When installed, walls in front of the fireplace must be a minimum 1" to the side of the fireplace.
- Due to the high temperature, the heater should be located out of traffic and away from furniture and draperies.
- Fireplace must be placed so the vents below and above the glass do not become blocked.

Raised Fireplaces

• The fireplace (and hearth, if desired) may be placed on a platform designed to support the fireplace (225 Lbs.) and vent.




Minimum Framing Dimensions - Rear Vent Configuration



The on/off switch/thermostat wire (if used) should be routed to a location near the right front of the fireplace.

Minimum Framing Dimensions - Top Vent Configuration




The on/off switch/thermostat wire (if used) should be routed to a location near the right front of the fireplace.

Installation (for qualified installers only)

Nailing Brackets

There are four nailing brackets on the front of the fireplace.
Follow the directions below to prepare the nailing brackets.
Once in place, nail or screw the nailing brackets to the framing.


NOTE: Additional nailing brackets are provided along the base of the fireplace.
Use these brackets if not using the front brackets.





: Make sure the fireplace is square and plumb when placed in the framing. Measured corner-to-corner, the fireplace should be square (approx. 54-7/8" for each dimension). Use shims to insure the fireplace is square.

1/2" Drywall

For installations using 1/2" facing fold the larger tab out 90° (use a screwdriver if necessary).










5/8" Drywall

For installations using 5/8" drywall fold the shorter tab out 90° (use a screwdriver if necessary).









Corner Installations - Rear Vent Configuration

A typical 45° installation uses the framing dimensions shown in the illustration below (NOTE: all clearances still apply).



Corner Installations - Top Vent Configuration

A typical 45° installation uses the framing dimensions shown in the illustration below (NOTE: all clearances still apply).



Gas Line Requirements

MASSACHUSETTS INSTALLATIONS - WARNING:

THIS PRODUCT MUST BE INSTALLED BY A LICENSED PLUMBER OR GAS FITTER WHEN INSTALLED WITHIN THE COMMONWEALTH OF MASSACHUSETTS.

OTHER MASSACHUSETTS CODE REQUIREMENTS:

- Flexible connector must not be longer than 36 inches.
- Shutoff valve must be a "T" handle gas cock.
- Only direct vent sealed combustion products are approved for bedrooms or bathrooms.
- Fireplace dampers must be removed or welded in the open position prior to the installation of a fireplace insert or gas log.
- A carbon monoxide (CO) detector is required in the same room as the appliance.
- The gas line must be installed in accordance with all local codes, if any; if not, follow ANSI 223.1 and the requirements listed below.
- The fireplace and gas control valve must be disconnected from the gas supply piping during any pressure testing of that system at test pressures in excess of 1/2 psig. For pressures under 1/2 psig, isolate the gas supply piping by closing the manual shutoff valve.
- Leak test all gas line joints and the gas control valve prior to and after starting the fireplace.

Fuel

 This fireplace is designed either for natural gas or for propane (but not for both). Check the sticker on the top of the gas control valve to make sure the correct fuel is used.

Gas Line Connection


• Installation must be performed by a qualified installer, service agency or the gas supplier (In Massachusetts a licensed plumber/gasfitter).

Gas Inlet Pressure	Standard Input Pressure	Minimum Input Pressure	Maximum Input Pressure
Natural Gas	7" W.C. (1.74 kPA)	3.5" W.C. (0.87 kPA)	13.85" W.C. (3.45 kPA)
Propane	13" W.C. (2.73 kPA)	8" W.C. (1.99 kPA)	14" W.C. (3.48 kPA)


- If the pressure is not sufficient, make sure the piping used is large enough, the supply regulator is adequately adjusted, and the total gas load for the residence does not exceed the amount supplied.
- The supply regulator (the regulator that attaches directly to the residence inlet or to the propane tank) should supply gas at the suggested input pressure listed above. Contact the local gas supplier if the regulator is at an improper pressure.

Gas Line Location


Left Side Gas Inlet (preferred)




You may remove this cover plate to install the gas line. The cover plate has a 7/8" diameter hole (covered with a push plug). By rotating the plate 180° the hole may be re-located. You may also secure the plate in a customized location using the self-drilling screws.



Right Side Gas Inlet






Travis Industries 4070201 100-01182_002

Electrical Connection (required)

- The electrical line to the grounded receptacle inside the fireplace must be installed by a qualified installer and must meet all local codes.
- Make sure the household breaker is shut off prior to working on any electrical lines.
- The fireplace must be properly grounded in accordance with local codes (or ANSI/NFPA 70-1987)
- The electrical line must be a min. 14 gauge, and supply 120 Volts at 60 Hz (2 Amps)

<u>Caution</u>: Label all wires prior to disconnection when servicing controls. Wiring errors can cause improper and dangerous operation.



Wall Switch or Thermostat Installation


Wiring Diagram (Millivolt System)



Do not connect 110-120 VAC to the gas control valve or wiring system of this fireplace. The switch must be installed by a qualified installer.


The included wall switch may be installed following the directions below. An optional thermostat may also be installed. It is attached to the gas control valve in the same manner.

<u>Caution</u>: Label all wires prior to disconnection when servicing controls. Wiring errors can cause improper and dangerous operation.




Wall Switch Installation

1. Attach the included wire to the gas control valve.



2. Determine a location for the wall switch (the wire is a maximum 25' long). Route the wire through the gas inlet hole (either side) to the junction box and attach following the directions below. Set the on/off switch on the appliance to "OFF" to control the appliance with the wall switch.




Vent Requirements

- The gas appliance and vent system must be vented directly to the outside of the building, and never be attached to a chimney serving a separate solid fuel or gas-burning appliance. Each direct vent gas appliance must use it's own separate vent system.
- In addition to the requirements listed here, follow the requirements provided with the vent.
- A firestop is required whenever the vent penetrates a wall, floor, or ceiling (passes through framing members). Horizontal vent less than 48" above the fireplace must use the Travis Firestop (sku 93006094 it incorporates a 3" clearance above, 1" clearance below and to the sides of the vent). Other penetrations only require a 1" clearance and may use a standard firestop (make sure the required 1" clearance is met).
- Always use the high-wind termination (if available from the vent manufacturer).

Vent Clearances

 The vent must maintain the required clearance to combustible materials to prevent a fire. Do not fill air spaces with insulation.

	Before 48" Rise	After 48" Rise
Sides	1"	1"
Above	3"	1"
Below Horizontal or 45° Section	1"	1"




Altitude Considerations

- This heater has been tested at altitudes ranging from sea level to 6,000 feet. In this testing we have found that the heater, with its standard orifice, burns correctly with just an air shutter adjustment.
- Failure to adjust the air shutter properly may lead to improper combustion which can create a safety hazard.
 Consult your dealer or installer if you suspect an improperly adjusted air shutter.


Approved Vent

- Rear vent configurations use 8" diameter Simpson Dura-Vent Model GS vent.
- Top vent configurations use 8" or 6-5/8" diameter Simpson Dura-Vent Model GS vent. If using 6-5/8" diameter vent, attach the 8" to 6-5/8" reducer (Travis part # 98900165) to the fireplace.



Vent Installation

- Slide the vent sections together and turn 1/4 turn until the sections lock in place.
- Screws are not required to secure the vent. However, three screws may be used to secure vent sections together if desired.
- High temperature sealant is recommended at the appliance starter section connection (use high-temperature silicone or Mill-Pac®).
- If disassembly is required, at time of re-assembly check to see if the vent creates a tight fit. If it does not, apply high temperature sealant to the joints of the affected sections.
- Horizontal sections require a 1/4" rise every 12" of travel
- Horizontal sections require non-combustible support every three feet (e.g.: plumbing tape)



Approved Vent Configurations


Restrictor Position

Intake and exhaust restrictors are built into the appliance to adjust the flow rate of intake air and
exhaust gases. Depending upon the vent configuration, you may be required to adjust the
restrictor positions. The charts for acceptable vent configurations detail the correct vent
restrictor positions.

Exhaust Restrictor Adjustment




If the diffuser is required to be in position # 2, you may wish to adjust the diffuser while the exhaust restrictor is removed.




Intake Restrictor Adjustment

The intake restrictor is shipped in position # 1 (open). To adjust the restrictor to postion # 2 (closed, follow the instructions below.

NOTE: The intake restrictor is accessed with the burner removed (see page 52).




Slide the intake restrictor down and re-tighten the screws to secure.



Diffuser Plate Adjustment

Certain vent configurations require the diffuser plate to be adjusted (refer to the approved vent configuration charts for details). Position # 1 is stock (bent). Position # 2 is flattened. See the directions below to change the diffuser to position #2.




Rear Vent Configuration with Horizontal Termination (no vertical rise)

• The termination must fall within the shaded area shown in the chart. Use the indicated restrictor and diffuser positions.


HINT: Travis Industries provides a minimum rear vent kit (sku 98900168). It includes a 4" section and a horiztontal termination cap.

Vent with No 45° Elbow




- Exhaust Restrictor Removed
- Intake Restrictor # 1 (stock)
- Diffuser Position # 1 (stock)
- Min. 4" Horizontal Section
- Max.48" Horizontal Section(s)


Vent with 1 45° Elbow



- Exhaust Restrictor Removed
- Intake Restrictor # 1 (stock)
- Diffuser Position # 1 (stock)
- Min. 4" Horizontal Section
- Max. 24" Horizontal Section(s)


See the charts above to determine maximum vent






Rear Vent Configuration with Horizontal Termination (with vertical rise)


- The termination must fall within the shaded area shown in the chart. Use the indicated restrictor and diffuser positions.
- Up to four elbows (45° or 90°) may be used.
- Only one horizontal elbow may be used.



Rear Vent Configuration with Vertical Termination


- The termination must fall within the shaded area shown in the chart. Use the indicated restrictor and diffuser positions.
- Up to four elbows (45° or 90°) may be used.
- Only one horizontal elbow may be used.






Top Vent Configuration with Horizontal Termination

- The termination must fall within the shaded area shown in the chart. Use the indicated restrictor and diffuser positions.
- Up to four elbows (45° or 90°) may be used.
- May use 8" or 6-5/8" diameter vent (see page for 21 details).
- Only one horizontal elbow may be used.



Top Vent Configuration with Vertical Termination

- The termination must fall within the shaded area shown in the chart. Use the indicated restrictor and diffuser positions.
- Up to four elbows (45° or 90°) may be used.
- Only one horizontal elbow may be used.
- May use 8" or 6-5/8" diameter vent (see page for 21 details).



This is considered a horizontal elbow (it does not matter whether it turns right or left). It may be a 90° or 45° elbow.

Termination Requirements

NOTE: Measure all clearances from the nearest edge of the exhaust hood.

A Minimum 9" clearance from any door or window

B Minimum 12" above any grade, veranda, porch, deck or balcony

C Minimum 3-3/8" from outside corner walls


D Minimum 0" from inside corner walls

E Minimum 11" clearance below unventilated soffits or roof surfaces

Minimum 18" clearance below ventilated soffits

Minimum 6" clearance below roof eaves

NOTE: Vinyl surfaces require 24"



G Minimum 48" clearance from any adjacent building

H Minimum 84" clearance above any grade when adjacent to public walkways or driveways NOTE: may not be used over a walkway or driveway shared by an adjacent building

I Minimum 48" clearance from any mechanical air supply inlet


J Minimum 36" clearance above and 48" below and to the sides of non-mechanical air supply inlet

K Minimum 36" from the area above the meter/regulator (vent outlet)

L Minimum 36" from the meter/regulator (vent outlet)


M Minimum 24" above the roof line (for vertical terminations)

N Minimum 24" horizontal clearance to any surface (such as an exterior wall) – for vertical terminations





NOTE: Measure clearances to the nearest edge of the exhaust hood.

- Use the vinyl siding standoff (#950) when installing on an exterior with vinyl siding.
- Vent termination must not be located where it will become plugged by snow or other material.
- · Venting termination shall not be recessed into a wall or siding.
- These clearances meet UMC-1994 code standards.



Hearth Requirements







Facing Requirements

- This appliance is designed to allow for drywall (or other combustible facing) to contact the sides and top of the front of the fireplace.
- Non-combustible facing (tile, masonry, etc.) must be placed over the fiber board on the front of the fireplace (see "Facing Overview" on page 34 for further details).

Drywall Installation





Facing Overview




Upgrade faces are available for this fireplace and may influence facing installation. Consult with your Travis Dealer if you are using an upgrade face.

Optional non-combustible facing may be installed on the fireplace. Use the guidelines below to determine the location (also see the following pages for detailed diagrams.

<u>Tile Line</u> Any non-combustible facing under 1" thick (see "Thin Facing" on page 35).

Masonry Line Any non-combustible over 1" thick (see "Thick Facing" on page 37).

Hearth Line Non-combustible hearth/facing should be installed up to this location (1" above the base of the fireplace). The fireplace may be raised to accommodate thicker hearth materials.




Optional Faceplates – Sizing Chart

<u>Name</u>	Height	Width	<u>Notes</u>
FPX Artisan, Classic, Fr Ctry	35-3/4"	41"	45-3/4" Radius – May fit over top of tile facing
Winthrop Victorian Lace	34-1/8"	36-7/8"	Optional facing will butte to edge of faceplate (tile line)
Wilmington Hearthview	35-3/4"	41"	May fit over top of tile facing
Winthrop Bungalow	34"	36-7/8"	Optional facing will butte to edge of faceplate (tile line)


Thin Facing Installation (tile, marble, or other non-combustible under 1" thick)




Upgrade faces are available for this fireplace and may influence facing installation. Consult with your Travis Dealer if you are using an upgrade face.



Thin Facing Installation (tile, marble, under 1" thick) - Side View






Thick Facing Installation (stone, brick, or other non-combustible over 1" thick)



If using a Fireplace Xtrordinair (FPX) arched face, see "Thick Facing with a Fireplace Xtrordinair Arched Faces" on page 38.




Thick Facing with Fireplace Xtrordinair (FPX) Arched Faces




The following illustration shows facing considerations for those fireplaces utilizing FPX arched faces. The facing must be non-combustible and over 1" in depth.


The Fireplace Xtrordinair 864
Masonry Template is
recommended for masonry
installation (sku 98500688). The
template helps locate and
support the masonry as it being
installed.






TOP VIEW







Masonry is installed 1" (maximum) above the base of the fireplace.




Thick Facing Installation - Side View





Mantel Requirements

- Use the table below to determine the maximum mantel depth allowed. The mantel depth (measured from the face of the fireplace) must fall in the shaded portion of the table.
- Any facing material that protrudes more than 3/4" from the face of the fireplace is considered a
 mantel and must meet the mantel requirements.




Examples: • If you wish to have a 8" deep mantel, it must be at least 12-1/4" above the fireplace face (49" above the base).


• If you wish to have a mantel 8" above the fireplace face, it must be no deeper than 3-3/4".

Installation Example - Build-Out (Dog-House) with Horizontal Termination

The framing, facing, and other building materials depicted below are for example only. Refer
to local building codes for framing, facing, and insulating requirements in your area.




Top View



Installation Example - Build-In with Horizontal Termination

The framing, facing, and other building materials depicted below are for example only. Refer
to local building codes for framing, facing, and insulating requirements in your area.



Top View

NOTE: 1/2" Clearance to sides and back of fireplace. NOTE: If required to use drywall inside the firebox enclosure, make sure to alter the framing accordingly. Drywall Optional Tile

Steps for Finalizing the Installation

1. Remove the glass (see page 45).

NOTE: If using propane (LP) convert the appliance prior to installing the logs.

- 2. We recommend you purge the gas line at this time (with the glass removed). This allows gas to be detected once it enters the firebox, ensuring gas does not build up.
- 3. Install the logs (see page 47).
- 4. Turn on the gas to the fireplace. Turn on gas to the heater. Leak test all gas joints prior to starting the appliance. Start the pilot.

Starting the Pilot Flame

<u>WARNING</u>: When lighting or re-lighting the pilot, the glass must be removed (see page 43).

- a Remove the glass.
- b Push the gas control knob in slightly and turn it to the "OFF" position. The knob will not turn from "ON" to "OFF" unless the knob is depressed slightly. Wait five minutes to let any gas that may have accumulated inside the firebox escape. If you smell leaking gas, follow the directions on the cover "IF YOU SMELL GAS".
- **c** Turn the gas control knob to the "PILOT" position and press the knob in, this will allow gas to flow to the pilot light. Press the button on the pilot igniter repeatedly until you see the pilot light.

<u>WARNING:</u> If the pilot does not light after 15 seconds, release the knob and call your dealer for service. Do not attempt to light pilot until service has been performed.


NOTE:

You may wish to remove the log set to gain a better view of the pilot (see page 47).

- **d** Keep the gas control knob depressed for 30 seconds once it is lit.
- **e** Release the gas control knob. If the pilot goes out, repeat step C. If the pilot refuses to stay lit, call your dealer for service. With the pilot lit, proceed to step "f".
- **f** Replace the glass.
- **g** Turn the gas control knob counter-clockwise to "ON". The pilot is now lit and the heater can be turned on and off.
- 5. Check the pilot flame following the directions below.

Pilot Flame Inspection

The pilot flame should look like the illustration below. Adjust the pilot flame if necessary.



The pilot flame must contact the thermocouple and thermopile (see the illustration below). Adjust the pilot up or down as necessary.

Replace the glass.


7. Start the main burner (the main burner circuit is detailed on page 20). Leak test all gas joints again.

Finalizing the Installation (for qualified installers only)

8. Check the air shutter following the directions below.


Air Shutter Adjustment

Let the heater burn for fifteen minutes (make sure the logs and glass are in place). The flames should be yellow with no sooting. Adjust the air shutter, if necessary, to achieve the correct looking flame.



Correct

Flames should be blue at the base, yellow-orange on the top.



Not Enough Air

If the flames are over 14" tall or sooty on the ends, open the air shutter.



Too Much Air

If the flames are all blue and short, close the air shutter.


Air Shutter Adjustment

The air shutters may be adjusted while the burner is on (take care to prevent contacting the burner area).

There are two air shutters on this fireplace - adjust both air shutters to obtain the correct flame.

Move the controls left or right until the flame looks correct. The rear air shutter affects the rear portion of the burner, the front air shutter the front portion of the burner. Pushing to the left gives the flame less air, making it more orange. Pushing to the right gives the flame more air, making it more blue.

NOTE: If the air control is all the way open, yet the flames remain sooty, shut off gas to the fireplace and contact a qualified gas service technician.



NOTE: The logs must be installed correctly to monitor the flame while adjusting the air shutter.

- 9. Turn the flame adjust knob to its highest position the flames should not contact the top of the firebox. Check the flame on low position. The flames should burn off of each burner hole. If the heater does not work correctly, contact your Travis dealer for a remedy.
- 10. Give this manual to the home owner for future reference and fully explain operation of this heater. For comprehensive operating and maintenance instructions, refer to the Owner's Manual (part # 100-01181).

ACID WASH WARNING: Before installing the faceplate, make sure any masonry that has been treated with acid wash has been properly neutralized (this is used primarily with brick faces). Acid wash (muriatic acid) is used to remove excess mortar. If not properly neutralized with an ammonia solution, the plated face may develop a permanent tarnish when the acid evaporates over time. Contact your dealer if uncertain your facing has been properly neutralized.

Glass Frame Removal and Installation

Warning: The appliance must be completely cool before removing the glass.

Warning: Do not strike or slam the glass.


(a)

Based upon the face being used, either:

(a) swing the access door down and remove the top grill,


(b) remove the face (unscrew or lift off - see the instructions included with the face for details).


Open the six latches holding the glass frame in place (start with the bottom three) - follow the directions shown to the right.





You may need to lift the glass frame while re-attaching.





Re-Attaching the Glass Frame:

pull it forward to remove.


- a) Hang the glass frame on the firebox.
- b) While holding in place, attach the upper latches (follow the instructions to the right in reverse).
- c) Lift the glass frame slightly and attach the lower latches.

NOTE: Make sure the glass frame is all the way in place - it should be flush with the front of the fireplace when installed.


Glass Frame Removal and Installation (continued)

The latch can come loose from the latch assembly. This occurs only when it is rotated. Follow the directions below to re-install the latch if it comes loose.


Hold the latch at an angle and insert it into the slot on the glass frame anchor.



Note how the washer on the latch fits behind the flange on the glass frame anchor.




Once fully inserted, turn the latch until it is upright.




Fireback and Grate Installation

WARNING: Firebacks are required for this fireplace and must be installed prior to operation.


- 1 Remove the glass frame.
- 3 Remove the exhaust restrictor (see page 23). Make sure to return the restrictor to the correct position after the firebacks are in place.
- 4 Install the firebacks and grate following the directions below.






Log Set Installation

Rear Log Installation



Right Log Installation



The burner has a flat portion here with a ridge directly behind it.


Place the right log on the flat portion of the burner and push it back so it rests against the ridge.


Note how the notch on the right log hangs over the side of the burner.

Rotate the inward tip of the log forward so it is directly next to the burner holes.

Travis Industries 4070201 100-01182_002


Left Log Installation






Finalizing the Installation (for qualified installers only)


Left Twig Installation



Right Twig Installation




Place the right twig so the hole fits over the pin on the rear log.




VERIFY REAR LOG POSITION

With all the logs in place, verify the rear log is vertical and all the way back – this will insure proper air flow and prevent sooting.

Center Twig Installation



Front Twigs Installation




Ember Installation

A bag of embers is provided to further enhance the firebox. Place the embers on the firebox floor and on the burner (especially over exposed screws on the burner). Do not place embers over any of the burner holes or air channels.


LP Conversion Instructions


Install the conversion kit prior to installing the gas line to ensure proper gas use.

- Remove the glass (see page 45). Remove the logs and coals (if installed page 47). Remove the grate and firebacks (see page 47).
- Remove the burner (see illustration below).




3 Follow the directions below to replace the orifices.





4 Remove the pilot orifice following the instructions below. Replace with the propane pilot orifice




Finalizing the Installation (for qualified installers only)

- 5 Replace the firebox components. Install the logs and embers. Replace the glass.
- 6 Remove the regulator from the front of the gas control valve. Replace with the propane regulator, using the new gasket and screws included with the regulator. NOTE: Leak test this area after the heater is installed, gas is connected, and the main burner is lit.
- 7 Make the gas line connection, bleed the gas line (if applicable), start the heater and thoroughly leak-test all gas connections and the gas control valve. Check the pilot (see the illustration below. Adjust if necessary.


WARNING: When lighting or re-lighting the pilot, the glass must be removed (see page 45).

(a) Remove and discard the three screws using a slotted screwdriver of Torx T-20. Slotted Screwdriver (or T-20 Torx) Remove and discard the regulator, diaphram, spring and center post. Install the LP regulator. Use the screws included with the LP regulator. Tighten to approximately 25 Lbs. torque. Slotted Screwdriver NOTE: Make sure the (or T-20 Torx) regulator gasket is correctly aligned before installation. Place the LP label on the base of the fireplace near the gas control valve.

To adjust the pilot flame, turn this screw (NOTE: if totally unscrewed gas will come out of this port). Clockwise lowers the flame while counter-clockwise raises it.



The pilot flame must contact the thermocouple and thermopile (see the illustration below). Adjust the pilot up or down as necessary.



Standard


Grill Installation

Certain faces allow for installation of an upper and lower grill. Follow the directions below to install.

Upper Grill Installation

Hold the grill at an angle and insert the lower slot over the bushing on the fireplace (both sides). You may need press on the grill to get the tab over the bushing (this prevents the grill from accidentally falling off).

Swing the grill upwards to engage the second slot. You will need to lift the grill slightly to get it over the bushing. Once in place the grill is held in place by gravity.




Hold the grill at an angle and insert the lower slot over the bushing on the fireplace (both sides). You may need press on the grill to get the tab over the bushing (this prevents the grill from accidentally falling off).

Bend this the tab over on both sides. This is the end-stop for the lower grill, it allows the grill to swing forward. Swing the grill upwards to engage the second slot. You will need to lift the grill slightly to get it over the bushing. Once in place the grill is held in place by gravity.


Remote Control Receiver Installation (2 Options)

The instructions below detail installation of the optional remote control receiver. For operating instructions, refer to the instructions included with the remote.

OPTION #1 - Remote Thermostat (99300653)



OPTION # 2 - Remote Thermostat (99300676)




Extra Room Power Heat Duct (sku 98500769)


Special Instructions for 864 HH

Newer 864 HH fireplaces (SN 3407-001010 or greater) have an improved wiring harness and removable heat shields below the heat duct connections. The wiring harness is now routed through the snap disk, allowing the power heat duct to be turned on and off by the fireplace (see "Wiring Instructions" on page 62). An additional knock-out was added to the fireplace to allow for the electrical line to be routed to the power heat duct (see below). The removable heat shields allow more heat to be routed to the power heat ducts (see below for details).


New Wire Hook-Up



New Removable Heat Shield (improves heat output to power heat duct)



Remove and discard the circular cover plate attached to the heat shield.



Installation Overview

The optional heat duct allows the fireplace to transfer heat to separate locations in the home. Installation should take place prior to installing drywall.

Warning: This kit must be installed as specified in these instructions. Do not modify any

component.

Warning: Use of any external blower other than the Travis Power Heat Duct Blower will void the

warranty and listing of this appliance and may create a fire hazard.

Note: The power heat duct <u>must</u> be installed by a qualified service technician.

Note: Some building codes may require the use of firestop spacers whenever the duct passes


from room to room.

Note: When routing ducts through a cold area (e.g. crawl space) we recommend insulating

the duct with fiberglass insulation. If paper-backed insulation is used, the paper can


not contact the duct.

Note: One or two het duct kits may be used.




Duct Installation Instructions

Determine the route for the heat duct using the illustration below as a guide.




Attach the blower box to the framing or floorboards of the home following the instructions below.

Wall or Ceiling Mounting




^{*} This blower was designed for framing on 16" centers. Construct additional framing if needed. If the blower is installed prior to the drywall only a 14" opening is required. If installed after the drywall is in place, the drywall to the sides of the blower will need to be patched.


Floor Mounting





Attach the floor boot to the blower box with the included screws.







The screws attach to either of these pairs of holes. Use the upper pair for thick flooring, the lower pair for thin flooring.



Slide the blower into the hole cut in step "a". Attach with four screws.




Attach the starter ring to the fireplace following the directions below (use the most convenient side - 864TRV has only one opening on the right side).




Install the air duct. Each section, when joined, must be attached with three screws and aluminum duct tape (U.L. 181A-P or equivalent). Secure the duct if it is in an area where it may sag or become dislodged.

NOTE: The air duct has a 0" clearance to combustibles.




Attach the grill (and wall adapter, if necessary).




Wiring Instructions

<u>Warning</u>: All wiring should be done by a qualified electrician and shall be in compliance with local codes and with the current National Electric Code ANSI/NFPA 70.


Warning: Make sure the fireplace electrical circuit is disabled prior to working on electrical hookup.



1 Follow the directions below to wire the blower box.




Attach the hot (black) and common (white) wires to the leads coming from the wires (use wire nuts).




2 Follow the directions below to wire the rheostat. **NOTE:** There are two types of junction boxes, use the appropriate junction box for your installation.




Force the sheathed cable through one of the locking flaps on the junction box (repeat for the other cable). Some force is needed. The flap will lock the cable in place.



Attach the common (white) wires together. Attach the ground (exposed or green) wires together. Then attach each of the hot (black) wires from the cables to the two wires on the rheostat (orientation does not matter). Carefully pack the wires into the junction box.



Attach the cover plate
(either white or beige) with
the included screws. Slide
the knob (either white or
beige) over the rheostat



Run the free wire from the rheostat junction box to the power supply. The thermodisk included with this kit may be discarded (it is not used on this fireplace).

Operating Instructions

To Power Supply (864TRV)

Allow the fireplace to reach normal operating temperature. Then use the wall-mounted rheostat to operate the blower speed.

864TRV: Turn the blower off when the fireplace is not in operation.

OFF

Turn the dial all the way counterclockwise until it clicks off.

HIGH

The high position is all the way counterclockwise, <u>without</u> clicking off.

LOW

Turn the dial all the way clockwise.




MAINTENANCE INSTRUCTIONS

Once a year the grill should be removed and the blower area cleaned. Use a vacuum to clean around the squirrel-cage blower, being careful not to damage any of the blades.







Accent Light Installation (sku 94400100)



Make sure power to the fireplace has been turned off prior to installation (disable the service breaker).




Do not connect 110-120 VAC to the gas control valve or the on/off circuit on this fireplace.




The accent light must be removed to install the rear fireback. The remaining firebacks are installed after the accent light is in place.

- 1 Remove the firebacks (if already installed see page 47). Remove the burner (see 52 for details).
- 2 Remove the cover plate following the directions below.




3 Place the rear fireback in position and install the accent light assemblies following the directions below.



Travis Industries 4070201 100-01182_002

4 Install the strain relief plate to the firebox floor following the directions below.




5 Restore the firebox to the correct configuration (replace the burner, firebacks, logs).



If using the optional wall-mounted rheostat, follow the directions on the following page "Wall Mounted Rheostat".

6 Install the rheostat assembly following the directions below.




Optional Equipment (for qualified installers only)

Optional Wall-Mounted Rheostat



NOTE: Many areas require all wiring to be installed by a qualified electrician. Check with your local building official for any requirements in your area.


- 1 Remove the rheostat from the rheostat assembly.
- 2 Detach the three wires leading from the rheostat (secured with wire nuts). Attach the rheostat assembly to the fireplace (see the illustration on the previous page). Attach the quick connects from the rheostat to the quick connects from the accent light assemblies (see the illustration on the previous page).
- Attach three suitable wires (insulated & sheathed) to the rheostat. Install the rheostat into a junction box at the remote location. Run the wire from the junction box to the fireplace. Use the included wire clamp to secure the wiring as it passes through the fireplace (see the illustration below).
- 4 Connect the three wires from the rheostat to the three wires on the wiring harness disconnected in step 2 (use the included wire nuts). Plug the rheostat assembly into the receptacle inside the fireplace.



Accent Light Operation

NOTE:

The accent light responds best when turned to high, then turned down to the desired light level.



Index

Index

Additional Items Required7	
Air Shutter Adjustment44	
Altitude Considerations21	
Approved Vent Configurations23	
Approved Vent22	
Clearances11	
Converting the Fireplace to Top Vent Configuration 9	
Corner Installations - Rear Vent Configuration 15	,
Corner Installations - Top Vent Configuration 16	j
Diffuser Plate Adjustment25	,
Dimensions6	
Drywall Installation33	,
Electrical Connection (required)19)
Exhaust Restrictor Adjustment23	,
Facing Overview34	
Facing Requirements33	,
Features6	
Fireback and Grate Installation47	,
Fireplace Placement Requirements11	
Fuel 17	
Gas Inlet Pressure17	,
Gas Line Connection 17	,
Gas Line Location17	,
Gas Line Requirements17	,
Glass Frame Removal and Installation45	,
Grill Installation55	,
Hearth Requirements32	
Heating Specifications 6	
Index	
Installation Example - Build-In with Horizontal Termination. 42	
Installation Options 6	
Installation Overview7	
Intake Restrictor Adjustment24	
Listing Details2	
LP Conversion Instructions47	
Mantel Requirements40)
Massachusetts Requirements8	

Vinimum Framing Dimensions - Rear Vent Contiguration	12
Minimum Framing Dimensions - Top Vent Configuration	13
Nailing Brackets	. 14
Overview	. 2
Packing List	. 7
Pilot Flame Inspection	. 43
Extra Room Power Heat Duct	. 57
Raised Fireplaces	. 11
Rear Vent Configuration with Horizontal Termination (no vertical rise)	. 26
Rear Vent Configuration with Horizontal Termination (with vertical rise) $\ldots \ldots$. 27
Rear Vent Configuration with Vertical Termination	. 28
Recommended Installation Procedure	. 7
Remote Control Receiver Installation (2 Options)	. 56
Restrictor Position	. 23
Safety Precautions	. 4
Starting the Pilot Flame	. 43
Steps for Finalizing the Installation	. 43
Termination Requirements	
Thick Facing Installation with FPX Arched Faces	
Thick Facing Installation	
Thin Facing Installation	
Top Vent Configuration with Horizontal Termination	
Top Vent Configuration with Vertical Termination	
Vent Clearances	
Vent Installation	. 22
Vent Requirements	. 21
Wall Switch Installation	
Wall Switch or Thermostat Installation	. 20
Wiring Diagram (Blower and Power Heat Duct)	. 62
Wiring Diagram (Millivolt System)	. 20